

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 22

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5-S R 4-E B-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
 OCT 28 1994
 10:56 AM
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 26 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set 1/4 post Poplar 6 N 29 E 20, Poplar 3 N 8 W 21 July 1852, Section 31, T5S-R4E was subdivided as shown on survey in Satterthwaite record book but the monument was not described.
 Werner Sommer re-established it by setting an iron pipe in the pavement on a line between the NE corner Section 6, T6S-R4E and Southwest corner Section 31, T5S-R4E and the extension of the line between the North 1/4 corner and the occupied Center of Section 31, T5S-R4E and recorded in L. 4, P. 251 on August 17, 1979.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11-9-93, All trace of the monument was destroyed during road re-construction two years ago when the roadway was excavated 2'±.
 12-13-93 Set P.K. nail in pavement by retracing surveys done in Section 31, T5S-R4E and Section 6, T6S-R4E. October 6, 1994, removed P.K. nail and set 3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Dbl. hd. nail & disc in Elec. pole S 15° E 228.02
 NW corner of metal siding on Pole barn S 75° E 252.68
 SE corner of conc. block house foundation N 65° W 206.17
 SW corner of conc. wall (silage pit) N 75° E 283.97
 N 1/4 corner Sec 6, T6S-R4E West 321.01



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 29, 1994
 Signed by Glenn E. Richard Date Oct 19, 1994
 Glenn E. Richard
 Surveyor's Michigan License No. 13040