

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 23

For corners in
Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5 - S R 4 - E C-13
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

FILED
 OCT 28 1994 10:56 AM
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 26, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. June 1819, Joseph Fletcher set corner post W Oak 16 N 18 E 27, Ironwood 9 S 70 E 12.
 March 1882, James Blair couldn't find the corner and set stake and pieces of brick 5.44 ch East of the NE corner of Sec 6, T6S-R4E.
 J.L. Richard records from early 1900's called for stake and bricks.
 October 1971, Werner Sommer re-established the corner with an iron pipe in the pavement in line of fence North and on line between the Northwest corner and North 1/4 corner of Section 5, T5S-R4E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 11-9-93, All trace of the monument was destroyed during road re-construction two years ago when the roadway was excavated 2'±.
 12-13-93 Set P.K. nail in pavement by retracing surveys done in Sections 31 & 32, T5S-R4E and Sections 5 & 6, T6S-R4E.
 October 6, 1994, Removed P.K. nail and set 3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" X 4' iron pipe capped G.E. R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Fd. dbl. hd. nail & disc in 36" stump North 110.80
 Fd. dbl. hd. nail & disc in Tel. pole S 80° E 204.28
 NE corner of house foundation S 45° E 114.79
 NW corner of garage foundation S 20° E 117.93
 NE corner of house foundation N 50° W 173.75
 NE corner of Tel. pedestal S 65° W 133.12
 NE corner Sec. 6, T6S-R4E, West 379.21



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 29, 1994
 Signed by Glenn E. Richard Date Oct. 19, 1994
 Glenn E. Richard
 Surveyor's Michigan License No. 13040