

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee
(County)

Located In:

Corner Code #

LIBER 1 PAGE 330

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

1 SEP 1999 5:43:03 PM

VICTORIA J. DANIELS

REGISTER OF DEEDS
Register of Deeds Stamp & File Number

1. Public Land Survey	T - 5-S	R - 4-E	E-10
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on August 16, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1819 Joseph Fletcher set 1/4 section post W. Oak 30 S 3 W 70 Poplar 12 N 19 W,31
- 1837 Boughton subdivided Section 29 (type of monumentation not given)
- 1951 Kenneth Suydam and I set a spike in line with fence to east @ split of road fences
- 1955 Kenneth Suydam found the spike was gone and set a iron rod
- 1966 I found a iron pipe in the pavement
- 1972 I found a iron pipe in the pavement and recorded it in L 2, P 31
- 1982 I found a iron pipe in the pavement and recorded it in L 5, P 81
- 1994 I found 1/2" rod in iron pipe (Road re-construction starting)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

August 16, 1999 Found P.K. nail in the pavement 0.02 south and 0.02 west of found iron pipe 14" deep. Drove the iron pipe down with 5/8" X 3' re-rod in top with re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd. nail & disc in NW face EP N 20° E 106.11
- Fd. dbl hd nail & disc in W face EP S 20° E 94.51
- Fd. dbl hd nail & disc in W face EP N 20° W 69.03
- Fd. iron pipe West 32.94
- Fd. re-rod west 59.39
- The corner is 3.5± west of pavement centerline



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040