

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **24**

or corners in
Lenawee Located In: Corner Code #
 (County)

Public Land Survey T 5 - S R 4 - E Corner Code # E-13
 T R
 T R
 T R

Property Controlling S T R
 in Section S T R
 Miscellaneous S T R
 Property in Sec. S T R

FILED 10:56 AM
 OCT 28 1994
 LENAWEЕ COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Glenn E. Richard, in a field survey on September 26 1994,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set post corner Sections 32 & 33, W Oak 10 N 74 E 49, W Oak S 84 E 40
 Shown on Plat of Tecumseh Acres, recorded in Liber 9 of Plats, Pages 42 and 43, February 11, 1948.
 July 17, 1975, I dug and found boat spike 10" below the pavement, which agreed with the Plat of Tecumseh Acres,
 and raised with 1" iron pipe, recorded it in L. 3, P. 292, SE. Corner of store N 40° W 77.59.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 23, 1994, Found 1" iron pipe.
 October 7, 1994, Found boat spike under iron pipe, set 3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument
 box.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the
 position of the original corner.

SE corner of brick on store building N 40° W 77.55
 Dbl. hd. nail & disc in Elec. Pole N 75° W 129.35
 Dbl. hd. nail & disc in Elec. Pole S 80° W 183.05
 Dbl. hd. nail & disc in Tel. Pole S 40° E 31.60



Witnessed by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 29, 1994
 Witnessed by Glenn E. Richard Date Oct. 19, 1994
 Glenn E. Richard

Surveyor's Michigan License No. 13040