

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 58

**FILED**

DEC 05 1994

*2:01 P.M.*

LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Lenawee Located In: Corner Code #  
(County)

1. Public Land Survey T-5-S R-4-E G-13  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. June 1819, Joseph Fletcher set post Corner Sections 33 & 34, W Oak 10 S 49 E 104, W Oak 12 N 47 E 139.  
J.L. Richard records, January 31, 1919 " Found 6.35 East of east rail ".  
1957-58, K.L. Suydam shows a point in his notes 8.70 east of RR. track center line.  
The corner is shown on Assessor's Plat No. 6, City of Tecumseh, recorded in L 14 of plats, Pages 15, 16 and 17, in 1958.  
1967, I dug and found iron pipe 6" below the pavement 6.04 East of east rail.  
April 8, 1976, K.L. Suydam recorded the corner in L 3, P 383.  
June 2, 1978, found empty monument box after re-construction of road. Dug up pavement using remaining witnesses and found iron pipe 12" deep 1'± Southwest of monument box, set iron pipe in pavement which checked 6.04 to east edge of rail.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 21, 1994, Found iron pipe in pavement 6.05 East of east rail.  
November 16, 1994, Moved monument box to correct location. Found original iron pipe 12" deep. Couldn't remove it so drove it down and set 3/4" X 3' iron pipe capped G.E.R. P.S. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe in monument box capped G.E.R., P.S. 13040 and is accepted as the best available evidence of the position of the original corner.  
Dbl. hd. nail & disc in Elec. pole N 70° W 77.69  
Dbl. hd. nail & disc in Tel. pole N 10° W 63.86  
Dbl. hd. nail & disc in Elec. pole N 75° E 65.96  
NW. corner of brick building S 30° E 112.07  
East edge of east rail West 6.05



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 29, 1994  
Signed by Glenn E. Richard Date Nov. 29, 1994  
Glenn E. Richard

Surveyor's Michigan License No. 13040