

RECORDED  
 JAN 25 2000  
 SECTION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 313  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 5-S R - 5-E	G-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

14 JUL 1999 6:30:44 PM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on June 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	●	3	2	1						
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 G.L.O. 1819 Joseph Fletcher set 1/4 Sec. post Elm 10 North 14 Sugar 7 S 50 W 23  
 1834 Satterthwaite Subdivided Section 4  
 1882 James Blair "Found Corner"  
 1980 Kenneth Suydam RLS 17636 found iron and recorded it in L 5 P 28  
 1997 I found iron pipe in monument box and witnessed  
 1999 Mike Bartolo set P.K. nail in the pavement from my witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 June 23, 1999 I found P.K. nail in the pavement over a iron pipe in a monument box which was 3" under surface of pavement. Replaced the iron pipe with 5/8" X 3' re-rod and raised the box with adjusting ring.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
 dbl. hd. nail & disc in S. face of 16" Walnut East 30.25  
 "X" cut on N. end 6" steel culvert S 75° W 25.61  
 "X" cut on S. end 6" steel culvert S 30° W 47.31  
 "X" cut on top of large granite boulder N 85° W 35.47



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999  
 Signed by Glenn E. Richard Date July 8, 1999  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040