

JAN 25 2000

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 314

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

14 JUL 1999 6:30:56 PM

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T - 5-S R - 5-E G-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- In Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec S _____ T _____ R _____

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on June 23, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1819 Joseph Fletcher set post cor. Sec.'s 3, 4, 9 & 10 Hickory 10 S 43 W 11 Lynn 12 S 47 E 22
- 1882 James Blair "Found Corner" and described it as iron bar, stones & brick.
- 1910 J.L. Richard found strap rail and stone
- 1928 Walter Frazier found stake & stones. Added iron pipe
- 1971 AES found boat spike in monument box
- 1972 Kenneth Suydam RLS 17636 found iron pipe? in monument box and recorded it in L 4 P 295
- 1997 I found boat spike in monument box and raised box with adjusting ring
- 1999 Mike Bartolo found boat spike in monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 23, 1999 I found boat spike in monument box and "strap rail" on top of stone 24" deep. Bent the bottom 12" of the 5/8" X 3' re-rod & drove it with the bent bottom on the north side of the stone.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod over stone with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd 60d spike in 48" Maple S 80° W 128.62
- Fd dbl hd nail & disc in 24" pipe S 40° E 76.45
- N.W. corner of stone foundation. House #10015 S 35° E 123.67
- Cut "X" on concrete foundation of silo N 50° E 118.54



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040