

JAN 20 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 316

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

14 JUL 1999 6:31:22 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

SECTION

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey	T - 5-S	R - 5- E	G-5
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on July 6, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. 1819 Joseph Fletcher set post cor. Sec. 9, 10, 15 & 16 Elm 12 S 5 E 16 Elm 13 S 20 W 12  
1930 Notes on survey by W.E. Frazier describe the corner as "Lost"  
1968 W. E. Frazier & Associates did a survey in Sec. 15 & sighted to point in intersection without monumentation  
1973 W.E. Sommer re-established the corner and recorded it in Liber 2, Page 321 (location of 1968 by W.E. F. & Associates may be different) (L 2, P 321 states IP but field notes state iron pin)  
1974 W. E. Frazier & Associates found iron bar  
1990 W.E. Frazier & Associates did survey in SE corner of the NE 1/4 of Section 16 and sighted to the recorded corner.  
1997 I found a 1" X 9" iron bar under newly layed asphalt pavement, replaced it with a 3/4" X 3' iron pipe and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
July 6, 1999 Found 3/4" iron pipe in monument box. Drove the iron pipe down with 5/8" X 3' re-rod inside of it and capped with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner  
N.E. cor. of conc. curb under guard rails N 75° W 49.33  
S.E. cor. of conc. curb under guard rails S 80° W 49.36  
Cut "X" on CMP N 15° W 68.15  
Cut "X" on CMP N 25° E 75.93  
Survey mark spike & re-mon tag in E.P. S 35° E 58.71  
fd dbl hd nail & disc in T.P. S 45° W 41.97



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040