

JAN 25 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1

PAGE 318
STATE OF MICHIGAN
LENAWEE COUNTY

SECTION

FILED

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T - 5-S R - 5-E G-7
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec S T R

14 JUL 1999 6:31:48 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on July 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher set post corner Sec.'s 15, 16, 21 & 22 W. Ash 14 N 68 E 21 Sugar 4 S 59 W 10
 1965 +/- Jack Gillin (Len. Co. Rd. Comm.) found iron pipe
 1973 K.L. Suydam RLS 17636 re-established the corner and recorded it in L 4 P 293
 1973 AES found R.R. spk & measured angle in SW corner Section 15 and distances to 1/4 corners N. & E.
 1974 W. E. Frazier & Assoc. found P.K.
 1994 Steve Young retraced the AES 1973 survey in Sec. 15 and set a P.K. nail for the corner
 1997 I found the P.K. nail & dug 3' deep. Also probed deeper & in all directions but found nothing. Set 3/4" X 3' iron pipe and monument box in newly layed asphalt pavement.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 6, 1999 Found 3/4" iron pipe in monument box. Drove the iron pipe down with 5/8" X 3' re-rod inside of it and capped with Lenawee County re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd "X" cut on CMP S 55° E 38.02
- Fd "X" cut on CMP S 55° W 32.94
- Fd "X" cut on CMP N 20° E 58.15
- Fd dbl hd nail & disc in 17" Hickory N 10° E 116.35
- SW cor of brick face on Hse #10100 N 55° E 139.44



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040