

FILED

JAN 25 2000

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 319

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

14 JUL 1999 6:32:00 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - <u>5-S</u> R - <u>5-E</u>	<u>G-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. 1819 Joseph Fletcher set 1/4 Sec. post Hickory 9 S 44 W 11 Hickory 10 S 48 W 19
 Couldn't find any information on this corner in all of the old survey records.
 1958 Kenneth Suydam set a boat spike in line of fence to west on the southerly extension of R.O.W. irons on a lot to the north on the east side of the road which he surveyed in 1955
 1964 I found a iron pipe on west R.O.W. & set a boat spike 33' east at record angle from SE corner of Section 21
 1967 The boat spike was gone. I set a iron pipe by same method I used in 1964. Found small boat spike in face of E.P. west 36.14
 1973 W.E. Sommer found iron pipe & recorded it in L 2 P 469
 1974 W.E. Frazier & Associates found iron pipe
 1997 I found iron pipe under newly layed asphalt pavement and set monument box over existing iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 July 6, 1999 Found 3/4" X 19" iron pipe in monument box. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner
 Fd. small boat spike in face of E.P. S 85° W 36.29
 Brick face of hse #9474 S 60° W 108.29
 Brick face of hse #9473 S 65° E 144.14
 Brick face of hse #9481 N 70° E 142.24
 Fd dbl hd nail and disc in 18" Maple 59.96



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999
 Glenn E. Richard

Surveyor's Michigan License No. 13040