

JAN 25 2000

SECTION

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 321  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

14 JUL 1999 6:32:26 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in  
Lenawee  
(County)

Located In: Corner Code #

1. Public Land Survey	T - 5-S	R - 5-E	G-10
	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on July 6, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1819 Joseph Fletcher set 1/4 Sec. post Elm 12 N 61 W 23 W. Ash 12 S 27 E 24  
 Couldn't find any information on this corner in all of the old survey records.  
 1974 K.L. Suydam RLS 17636 re-established the corner and recorded it in L 4 P 294  
 1997 I found iron pipe under newly layed asphalt pavement. Replaced the FIP with 3/4" X 3' iron pipe and set monument box.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 6, 1999 Found 3/4" iron pipe in monument box. Drove the iron pipe down with 5/8" X 3' re-rod inside of it and capped with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

dbl hd nail & Lenawee County re-mon tag in 41' Aspen tree S 10° E 125.12  
 dbl hd nail & Lenawee County re-mon tag in E.P. N 45° E 221.14  
 SW corner of conc. block bldg. East 217.09  
 dbl. hd nail & disc in 20" Maple S 35° E 67.90

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999  
 Glenn E. Richard

Surveyor's Michigan License No. 13040