

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 195

For corners in

Lenawee
(County)

Located In:

Corner Code #

- 1. Public Land Survey T-6-S R-1-E G-4
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec S T R

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

9 OCT 97 3:40 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 16, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815 Thomas Evans set 1/4 Sec. post Elm 9 S 54 E 18 W. Oak 9 N 55 W 28
1888 James Blair found iron bar inside of stone pump
J.L. Richard record "Added Tile" date unknown
1919 Walter E. Frazier surveyed Townley Hwy. "Found" and checked remaining witness (hickory stump) from Blair's survey. Cor. fence post SW 46.2 Cor. fence post SE 43.0
1933 W. E. Frazier "Located from Hwy. Survey"
1947 Point of beginning, Plat of Daytona Heights
1974 I found boat spike and recorded it in L 3, P 83.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7-16-97 I found short piece of iron pipe over boat spike and bricks and angle iron 2 1/2' deep. Set 3/4" X 3' iron pipe in monument box in location of found boat spike

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Survey mark spike & Re-mon tag in 8" Apple N 65° W 99.07
Fd dbl hd. nail & disc in E.P. N 25° W 45.41
Fd dbl hd. nail & disc in 16" Ash N 15° E 34.37
Fd dbl hd. nail & disc in E.P. S 30° E 59.06
FIP N 50° E 99.89

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997
Glenn E. Richard

Surveyor's Michigan License No. 13040