

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 196

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 8-S R - 1-E	G-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED
 9 OCT 97 3:40 P.M.
 VICTORIA J. DANIELS
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 16, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1815 Thomas Evans set post cor. Sec. 9, 10, 15 & 16 Poplar 4 N 14 E 14 Poplar 4 S 41 W 16
- 1919 Walter E. Frazier surveyed Townley Hwy. "Drove gas pipe"
- 1955 Dan & Joe Frazier (sons of W. E. Frazier) "Raised iron to surface with R.R. spike"
- 1956 Point of beginning for Plat of Apple Acres
- 1974 Found R.R. spike bent. Replaced with new R.R. spike & recorded it in L 3, P 83.
- 1996 I found R.R. spike in top of iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 10, 1997 I found a short iron pipe capped 33970 set Feb. 1997 by M. Bartolo over R.R. spike in top of Iron pipe 18" deep. Removed and dug deeper but didn't find anything else. Set 3/4" X 3' iron pipe at location of the found monumentation
 7-16-97 I set a monument box with top 1 3/4" above base course of new asphalt pavement

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
- Plat monument East 32.97
- Iron pipe East 49.92
- SW corner of house #5015 (foundation) N 30° E 172.31
- NW corner of house #5001 (foundation) N 75° E 78.68
- SW corner of house #5001 (foundation) S 70° E 79.82
- found dbl hd nail & disc in E.P. S 55° W 38.69



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept 19, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040