

OCT 21 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 197

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6-S R - 1 - E	G-6
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

9 OCT 97 3:41 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 16, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815 Thomas Evans set 1/4 Sec. post Buckeye 15 S 44 W 16 1/2 Ash 12 N 84 1/2 E 16
 Early 1900's J.L. Richard record "Found corner, tile & crockery"
 1919 Walter E. Frazier surveyed Townley Hwy. "Found" Didn't give type of monumentation
 1974 Found boat spike. Set I.P. 50' and 100' West (same line)
 1988 I set a iron pipe using the two I.P.'s 50' and 100' West
 May 1996 I found the iron pipe & took additional witnesses
 July 1996 I dug and found bent boat spike 1' deep and at 2' deep a 1/2" galv. pipe leaning to West over stone and another stone 0.5 +/- South. Set 3/4" X 3' gas pipe on west side of stone with top over stone. The road is under re-construction

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 10, 1997 Found iron pipe 1.5 deep and raised with 5/8" X 30" re-rod
 7-16-97 Found the re-rod under base course of asphalt and set monument box with top 1 3/4" above pavement to be level with final course of asphalt.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 30" re-rod capped G.E.R. 13040 over 3/4" X 3' iron pipe in monument box and is accepted as the best available evidence of the position of the original corner.
 Iron pipe West 49.93
 Iron pipe West 99.90
 dbl. hd. nail & S.C.S. Benchmark tag in E.P. S 15° W 115.73
 dbl. hd. nail & disc in E.P. N 10° W 189.92
 dbl. hd. nail & disc in E. P. S 30° E 101.28



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 9, 1997

Signed by Glenn E. Richard Date Sept. 19, 1997
 Glenn E. Richard

Surveyor's Michigan License No. 13040