

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 129

For corners in

Lenawee

(County)

Located In:

Corner Code #

- 1. Public Land Survey T - 6 - S R - 1 - E G-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

13 NOV 96 9:06 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 12 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Oct 1815 Thomas Evans set post corner Sec. 15, 16, 21 & 22, W. Oak 22 N 4 E 18, Oak 30 S 74 E 12 1/2
1919 W.E. Frazier surveyed Townley Hwy "corner found"
1961 M.D.O.T. found pointed rock and raised with brass plate
Nov. 1971 W.E. Sommer found the brass plate and recorded it in Liber 1, Page 65
Jan. 1975 I found the brass plate and recorded it in Liber 3, Page 85.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

July 12, 1996 Found brass plate under newly layed 2" of asphalt. Dug deeper and found pointed stone. Couldn't remove it so drilled 12" into the stone and set 1/2"X14" re-rod capped G.E.R. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" X 14" re-rod in top of stone capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
NW corner of brick church S 50 W 158.00
NE corner of brick church S 25 W 120.84
Found M.D.O.T. tag in 16" Maple S 45 W 44.93
Dbt. hd. nail & disc in E.P. N 45 W 41.70
Dbt. hd. nail & disc in 24" Maple S 45 E 58.62



Ratified by Peer Group in accordance with P.A. 345

Co. Rep. Glenn E. Richard

Date 8-6-1996

Signed by Glenn E. Richard
Glenn E. Richard

Date 10-11-96

Surveyor's Michigan License No. 13040