

SURVEY & REMONUMENTATION

MAY 16 1997

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **121**

For corners in

Lenawee
 (County)

Located in:

Corner Code #

- 1. Public Land Survey T 6-S R 1-E C-8
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

13 NOV 96 9:04 A.M.

JEANETTE D. KNOX
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Glenn E. Richard, in a field survey on July 12 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	34	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Oct 1815 Thomas Evans set 1/4 Section post Hickory 6 N 67 W 7 Cherry S 27 W 20
 1881 James Blair found large stone
 Early 1900's J.L. Richard records call for "large stone"
 1919 W.E. Frazier surveyed Townley Highway and found stone
 Nov. 1961 M.D.O.T. found pointed stone and raised with brass plate
 April 1973 K.L. Suydam found the brass plate and recorded it in Liber 2, Page 403
 May 1974 I found the brass plate and recorded it Liber 2, Page 653
 Dec. 1975 The Brass plate was torn out. I set short iron pipe from witnesses and recorded it in Liber 3, Page 81.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

May 19, 1995 The pavement had just been scarified and the iron was gone. I found the stone and the iron pipes I had set East and West in 1975 were still O.K.
 July 12, 1996 I found the stone with small drill hole 14" under the 1st course of asphalt pavement. Also a capped (D.E.E. 29245) re-rod 0.2 East. Couldn't remove the stone or re-rod. Drilled 10" into the stone and set 1/2" X 12" re-rod capped G.E.R. 13040. Set monument box with top 1 1/2" above the 1st course of asphalt. The Lenawee County Road Commission is to finish the 2nd course of asphalt on 7-15-96.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

12" re-rod in top of stone capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Iron pipe 2' ± South of fence West 50.03
 Iron pipe 3.5 ± North of fence East 49.93
 The corner is on line between the above two iron pipes
 Capped (D.E.E. 29245) iron East 32.99
 Dbl. hd. nail & Re-mon tag in 30" Walnut S 5° W 234.17
 Dbl. hd. nail & Re-mon tag in E.P. West 86.11
 Face of SW bolt of S. leg of radio tower N 45° E 253.88



Ratified by Peer Group in accordance with P.A. 345

Co. Rep. Glenn E. Richard Date 8-6-96

Signed by Glenn E. Richard Date 10-25-96
 Glenn E. Richard

Surveyor's Michigan License No. 13040