

COMMISSION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

APR 01 1996

LIBER **001** PAGE **88**

For corners in  
Lenawee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
 (County)

1. Public Land Survey T 6-S R 1-E G-10  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

**FILED**  
 NOV 22 1995 11:56 AM  
 LENAWEE COUNTY  
 JEANETTE D. KNOX  
 REGISTER OF DEEDS  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn Richard, in a field survey on June 9, 19 95,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. October 1815, Thomas Evans set post Beech 22 N 47° E 23 Beech 22 N 17° W 39  
 May 15, 1890 James Blair found a stone set on end  
 J.L. Richard records call for "Found 1919" Endpost E. 27.0 Endpost W. 27.4  
 1960 ± Lenawee Co. Road Commission set 5/8" iron rod from Witnesses.  
 December 24, 1974 I found iron rod in pavement, set iron pipe 50' East and West with corner  
 on line between them and recorded it in L. 3 P. 79.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

June 9, 1995 found 3/4" X 20" galv. pipe between cluster of stones and larger pointed stone 0.4 N and 0.4 W.  
 Replaced the 3/4" X 20" galv. pipe with a 3/4" X 3' gas pipe capped G.E.R. P.S. 13040 and set monument box.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3/4" X 30" iron pipe capped G.E.R., P.S. 13040 and is accepted as the best available evidence of the position of the  
 original corner.  
 N.W. corner of Garage foundation N 55° W 224.00  
 "X" cut on S. end of drive C.M.P. N 10° W 96.91  
 dbl hd nail in E.P. N 80° W 33.48  
 Iron pipe West 49.98 }  
 Iron pipe East 49.98 } The corner is on line between the iron pipes.



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-19-95  
 Signed by Glenn E. Richard Date 10-9-95  
 Glenn E. Richard  
 Surveyor's Michigan License No. 13040