

JAN 25 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 379  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T-6-S R-1-E	G-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

7 DEC 1999 1:04:32 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 21, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1815-16 Benjamin Hough D.S. Set post cor. Sec. 33 & 34 Maple 14 N 70 W 11 1/2 B. Ash ^ N 2 E 8 1/2  
1880 G.E. Kedzie, County Surveyor notes call for bricks & stake  
1891 James Blair County Surveyor notes call for stake & tile  
Found no other information on the corner between 1891 and 1999  
1999 Michael Bartolo re-established the corner by doubling the distance between the SW corner & South 1/4 corner and a line 33' north of the monumented line of Posey Lake Subdivision and recorded it in Liber 5, Page 382.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 21, 1999 Found 1/2" re-rod capped #33970. Dug through pavement to set monument box. Didn't find any trace of any other monumentation. Replaced the found 1/2" re-rod with 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd. nail & brass tag N. face 14" Oak S 60° E 49.80
- Fd. nail & brass tag N. face elec. pole S 45° E 67.28
- Fd. nail & brass tag E. face 30" Oak South 22.78
- Fd. nail & brass tag S. face 12" Hickory S 60° W 52.72
- Made chiseled cross on W. end 24" conc. culvert N 40° E 29.97



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040