

SURVEY & REMONUMENTATION

JAN 15 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 232

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

22 DEC 97 9:24 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

SECTION

For corners in

Lenawee
 (County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6-S</u>	R <u>2-E</u>	<u>G-8</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

A B C D E F G H I J K L M

1														
2	6	5	4	3	2	1								
3														
4	7	8	9	10	11	12								
5														
6	18	17	16	15	14	13								
7														
8	19	20	21	22	23	24								
9														
10	30	29	28	27	26	25								
11														
12	31	32	33	34	35	36								
13														

I, Glenn E. Richard, in a field survey on November 10, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 Hervey Parke set 1/4 Sec. post Beech 26 S 16 E 11 Beech 12 N 7 W 32
 Early 1900's J.L. Richard records call for gas pipe
 1955 W.E. Sommer and I dug and found a gas pipe 20" deep and raised with a Hex iron
 1990 Dug with back hoe and found the Hex iron 3' deep and raised with a 3/4" X 3.5' iron pipe
 1996 Steve Young found the iron pipe 7" deep under asphalt pavement and raised with 12" spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov 10, 1997 Found spike over 3/4" iron pipe capped G.E.R. Replaced with 3/4" X 3' iron pipe capped G.E.R. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Found Dbl. hd. nail & disc in 36" Ash East 25.96
 Found Dbl. hd. nail & disc in 10" Ash S 55° W 24.41
 Found Dbl. hd. nail & disc in 14" Walnut N 50° W 35.29
 Found "X" on S. end C.M.P. S 40° E 28.65



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97
 Glenn E. Richard

Surveyor's Michigan License No. 13040