

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990

LIBER 1 PAGE 282

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T-6-S R-2-E	1-7
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property In Sec	S T R	
	S T R	

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

25 SEP 1998 1:14:41 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Hervey Parke set post cor. Sec's 14, 15, 22 & 23 Beech 10 N 80 W 5 Beech 8 S 79 E 31
 Couldn't find any information on this corner
 1970 I dug and found piece of wood stake and pieces of brick and set a 1 1/2" iron bar
 1974 I found the 1 1/2" iron bar and recorded it in L2 P 583
 1975± Lenawee County Road Commission paved the road and set a monument box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 8, 1998 Found 1 1/2" X 27" iron bar in monument box. Replaced with 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Survey mark spike & re-mon tag in E.P. S 45° W 31.72
 dbl hd nail & re-mon tag in E.P. N 65° E 60.77
 dbl hd nail & re-mon tag in Maple N 45° E 72.29
 SE cor of house foundation N 70° W 262.50



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept. 23, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040