

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1 PAGE 281

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T -6- S R -2 - E	J -7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

25 SEP 1998 1:14:34 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 4, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 Hervey Parke set 1/4 Sec. post Beech 24 S 53 E 12 Beech 14 N 35 W 22
 Couldn't find any records that pertain to this corner
 1980 Werner Sommer did survey in the south 1/2 of Section 23. He didn't find anything at the N 1/4 corner and used computed point at midway between the NW and the NE section corners
 1997 Michael Bartolo set a 1/2" re-rod at midpoint between opposing section corners and recorded it in L 5 P 340

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 4, 1998 I found 1/2" re-rod under newly layed asphalt (9-3-98). Replaced it with a 5/8" X 3' re-rod and set monument box. The location of the corner is in a cut area.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Fd "X" cut on west end 12" CMP N 80° W 32.40
- Fd "X" cut on east end 12" CMP N 20° E 11.85
- Fd "X" cut on west end 12" CMP S 45° W 39.98
- Fd "X" cut on east end 12" CMP S 10° E 24.91



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept 23, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040