

SURVEY & REMONUMENTATION

OCT 19 1998

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 280

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Lenawee
(County)

Located in:

Corner Code #

1. Public Land Survey	T <u>6-S</u>	R <u>2-E</u>	<u>K-7</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

25 SEP 1998 1:13:55 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 8, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 Hervey Parke set post cor. Sec's 13, 14, 23 & 24 Beech 10 S 55 W 21 1/2
Beech 16 N 32 E 47
Couldn't find any old records that pertain to this corner
1980 Kenneth Suydam dug with back hoe and found stones and brick. Set 3/4" X 36" iron pipe and recorded it in L4 P 367
1988 Lenawee County paved the road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 8, 1998 Found 3/4" X 36" galv. pipe 8" deep under the pavement. Replaced with 5/8" X 36" re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County re-mon cap stamped 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Cut "X" on North end CMP S 80° W 130.30
- Cut "X" on North end CMP N 85° W 130.03
- Survey mark spike and re-mon tag in E.P. N 50° E 51.10
- Fd. nail & disc in post next to telephone pedestal S 50° E 46.88



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept. 23, 1998
Glenn E. Richard

Surveyor's Michigan License No. 13040