

JAN 6 2000

Filed under Remonumentation Act 345 of 1990

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

PAGE 389  
STATE OF MICHIGAN  
LENAAWEE COUNTY  
FILED

For corners in

Lenawee (County)	Located in:	Corner Code #
1. Public Land Survey	T - 6 - S R - 3 - E	B - 2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

14 DEC 1999 4:33:11 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on August 9, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. This corner was not monumented on the original government surveys  
 1991 I set a R.R. spike in the pavement at the intersection of the 1/4 lines and recorded it in Liber 5, Page 214  
 1992 Kenneth Suydam found R.R. spike

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Aug. 9, 1999 Found R.R. spike under base course of new asphalt pavement. Replaced with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- "X" cut on CMP drive culv. N 15° W 100.64
- "X" cut on CMP drive culv. N 12° E 87.69
- Iron pipe capped GER 13040 on 1/4 line East 33.02
- dbl. hd. nail & re-mon tag in E.P. S 15° W 119.34



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 7, 1999

Signed by Glenn E. Richard Date Dec. 8, 1999  
 Glenn E. Richard

Surveyor's Michigan License No. 13040