

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **29**

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T-6-S R-3-E B-3
 T. _____ R. _____
 T. _____ R. _____
 T. _____ R. _____

2. Property Controlling S. _____ T. _____ R. _____
 in Section S. _____ T. _____ R. _____

3. Miscellaneous S. _____ T. _____ R. _____
 Property in Sec. S. _____ T. _____ R. _____

FILED 10:56 AM
 OCT 28 1994
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 6 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set 1/4 post W. Oak 12 N 42 E 8, W. Oak 8 South 24
 J.L. Richard records from early 1900's called for iron and tile.
 1933 W.E. Frazier found corner 2 1/2' deep and set spike near surface 14" Elm N 23° E 60'.
 May 1962, I dug and found spike and raised it to the surface of the pavement.
 June 1965 I found a boat spike which checked the remaining witness and an iron pipe @ the 1/8 corner 1335' South.
 Nov. 1971, W.E. Sommer found the boat spike and recorded it in L. 1, P. 69, Dbl hd. nail in Elm stump N 25° E 60.20.
 March 1982, W.E. Sommer found iron pipe in monument box which checked to 1/8 corner south as found on the 1965 survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 6, 1994, Found iron pipe in monument box which checked witnesses taken on the March 1982 survey.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Cut "X" cut on C.M.P. N 50° W 36.84
 Cut "X" cut on C.M.P. N 50° E 38.18
 NW edge of gas line valve box S 50° E 47.24
 set dbl. hd. nail & disc in 10" Pine S 20° E 70.75



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
 Signed by Glenn E. Richard Date Oct 20, 1994
 Glenn E. Richard
 Surveyor's Michigan License No. 13040