

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE ELDER 1
 Filing Requirement of Act 74, Mich. P.A. 1970

PAGE **283**
 STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

For corners in Lenawee (County) Located In: Corner Code #

1. Public Land Survey	T <u>6</u> - S	R <u>3</u> - E	<u>B-7</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

25 SEP 1998 1:14:59 PM

VICTORIA J. DANIELS
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7	●												
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on September 8, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John M. Mack set 1/4 sec. post W. Oak 12 N 42 E W. Oak 8 S 24
 Early 1900's J.L. Richard's record stone above ground
 1963 Kenneth Suydam found the stone 3" out of the ground. Removed it, found bricks and set a 1 1/4" X 28" iron pipe
 1965 I set a iron pipe from witnesses of K.L. Suydam 1963 survey. The road had been rebuilt and cut 3 to 4 feet
 1975 Found iron pipe which checked the previous witnesses and recorded it in L 3 P 161
 1984 I found 3/4" X 15" iron pipe under pavement & raised with 3/4" X 30" iron pipe.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Sept. 8, 1998 Found 3/4" X 26" iron under newly layed asphalt pavement. Replaced it with a 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set a monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

Survey mark spike & Lenawee County re-mon tag in E.P. N 80° W 216.53
 Survey mark spike & Lenawee County re-mon tag in E.P. N 10° W 37.05
 Survey mark spike & Lenawee County re-mon tag in E.P. N 80° E 253.51
 dbl. hd. nail & re-mon tag in 18" Maple S 5 E 38.11
 Iron pipe N. 33.00



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date September 22, 1998

Signed by Glenn E. Richard Date Sept. 23, 1998
 Glenn E. Richard

Surveyor's Michigan License No. 13040