

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 375  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

7 DEC 1999 1:03:44 PM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

**SECTION**

For corners in Lenawee (County) Located In: Corner Code #

1. Public Land Survey T-6-S R-3-E B-9  
 T R  
 T R  
 T R

2. Property Controlling in Section S T R  
 S T R  
 S T R

3. Miscellaneous Property in Sec S T R

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on November 1, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	●												
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John M. Mack Set 1/4 Sec. post Sugar 10 S 5 E 17 Sugar 8 N 15 E 16  
 Early 1900's John L. Richard's record= "Stake in center of road"  
 1966 I dug and found old wood stake between two stones 24" under the pavement and raised to surface with 3/4" iron bar.  
 1973 Werner Sommer found 3/4" iron bar and recorded it in Liber 2, Page 367  
 1996 Steve Young found iron rod in monument box 6" under surface of asphalt pavement and raised with P.K. nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 1, 1999 Found P.K. nail at surface over 3/4" X 30" iron bar in monument box. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and raised the monument box with two adjusting rings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

dbl. hd. nail and disc in S.E. face of E.P. N 40° E 95.43  
 "X" on N. end CMP N 85° W 126.56  
 "X" on S. end CMP S 80° W 126.46

Lenawee County Re-mon corner C-9 T6S R3E in monument box East 2658.79



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999  
 Glenn E. Richard

Surveyor's Michigan License No. 13040