

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 30

For corners in

Lenawee (County)

Located In:

Corner Code #

- 1. Public Land Survey T-6-S R-3-E C-3
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

FILED

10:56 AM

OCT 28 1994

LENAWEE COUNTY JEANETTE D. KNOX REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on October 6 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 1-13. A dot is marked at row 3, column B.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set post. Sec. 5, 6, 7 & 8 Maple 8 S 35 E 86, Maple 4 N 87 W 4 J.L. Richard records from early 1900's called for "found stone & bricks 12" deep". 1933, W.E. Frazier found stone & bricks 14" Walnut North 32.0. May 1962, I dug and found stones & bricks and raised to surface with steel bar, top mushroomed. To face of 20" Walnut North 31.5, 8" Hickory S 25° W 27.65 and 12" Ash S 45° W 38.8. Nov. 8, 1971, W.E. Sommer found axle shaft and recorded it in L. I, P. 71, spike in 16" Walnut N 3° W 32.36, spike in 10" Hickory S 25° W 27.98, spike in 16" Walnut S 53° W 39.62. June 1976, I dug and found the axle shaft and raised with 3/4" X 18" iron pipe prior to paving by Lenawee County Road Commission.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 6, 1994, Found iron pipe in monument box, Replaced it with 3/4" X 3' iron pipe capped G.E.R., P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe, capped G.E.R. P.S. 13040 in monuement box and is accepted s the best available evidence of the position of the original corner. 60d spike in 24" Walnut N 5° W 32.36 60d spike in 12" Hickory S 20° W 27.98 NE corner Conc. house foundation S 60° W 95.74 Set dbl. hd. nail & disc in 8" Ash N 55° E 36.33 Set dbl. hd. nail & disc in Elec. pole S 5° E 100.97



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
Signed by Glenn E. Richard Date Oct. 20, 1994

Surveyor's Michigan License No. 13040