

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER 1

PAGE 376
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

For corners in

Located In:	Corner Code #
<u>Lenawee</u> (County)	
1. Public Land Survey	T-6-S R-3-E C-9
	T R
	T R
	T R
2. Property Controlling in Section	S T R
	S T R
3. Miscellaneous Property in Sec	S T R
	S T R

7 DEC 1999 1:03:55 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on November 1, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9	30	29	28	27	26	25							
10													
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John Mack Set post cor. Sec.'s 19, 20, 29 & 30 Hickory 8 S 31 W 2 Elm 14 N 45 E 50
Early 1900's John L. Richard's record= "Large Stone"
1920 Harold Clegg found stake and stone. Drove iron pipe
1973 I found iron pipe and recorded it in Liber 2, Page 479
1995 Michael Bartolo set P.K. over 1" pipe in monument box which was paved over

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 1, 1999 Found 1" X 14" iron pipe over stone in monument box. Set 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 on southeast side of stone and bent top to position of the found iron pipe. Raised the monument box with two 1 1/2" adjusting rings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Cut "X" on W. end concrete headwall N 65° W 34.57
Survey marker spike and Lenawee County Re-mon tag in E.P. S 40° E 39.30
N.E. corner of 4' X 4' fiberglass pedestal base S 10° W 126.91
Dbl. hd. nail & Lenawee County Re-mon tag in E.P. S 40° W 36.71
Lenawee County Re-mon corner B-9 T6S R3E in monument box West 2658.79



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040