

JAN 25 2000

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1

PAGE 377
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

SECTION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6 - S</u> R <u>3 - E</u>	<u>C - 10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

7 DEC 1999 1:04:08 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Glenn E. Richard, in a field survey on October 28, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John Mack Set 1/4 Sec. post Sugar 10 S 2 E 14 Sugar 6 N 14 E 10
 1958 I could not find any information on this corner prior to my re-establishing it while employed by Walter Frazier.
 "Did not find W 1/4 cor. Sec. 30. Set iron pipe in centerline of road fences" in line with fences East and West.
 1964 I found iron pipe and iron pipe west 33'
 1972 I found 1/2" iron pipe and recorded it in Liber 2, Page 61
 1995 Michael Bartolo found 1/2" iron pipe
 June 22, 1999 I found 1/2" iron pipe and witnessed as total road re-construction started.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Oct. 28, 1999 Iron pipe was gone and base course of asphalt had been layed. Set 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 and monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

NW corner of house foundation S 85° W 93.75
 SE corner of garage foundation N 40° E 281.75
 Re-rod on line of garage foundation N 40° E 129.57
 Re-rod in line with garage foundation S 40° W 62.17
 Found iron pipe capped GER East 33.05
 dbl hd nail & Lenawee County Re-mon tag in 10" Hickory N 40 W 57.44



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999
 Glenn E. Richard

Surveyor's Michigan License No. 13040