

**SURVEY &
REMONUMENTATION**

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **31**

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6 - S R - 3 - E	D-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

FILED

10:56 AM

OCT 28 1994

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3		●											
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 8 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C.L.O. January 1824, John Mack set 1/4 Sec. post B. Ash 11 N 36 W 16, Hick 6 S 52 E 11
1976, I couldn't find any record of this corner ever being found. Dug with back hoe but found nothing, Set 3/4" X 4' iron pipe on a straight 1/2 way between SW and SE corners of Section 5 which lined up with traces of old fence line South and recorded it in L. 3, P. 324.
"X" cut on C.M.P. N 40° E 22.94
"X" cut on C.M.P. S 60° E 40.97
"X" cut on C.M.P. S 30° E 22.06

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 8, 1994, Found 3/4" iron pipe in monument box, Replaced it with 3/4" X 3' iron pipe capped G.E.R., P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe, capped G.E.R. P.S. 13040 in monument box, and is accepted as the best available evidence of the position of the original corner.
Fd. "X" cut on C.M.P. N 40° E 22.94
Cut "X" on C.M.P. N 80° E 39.32
Fd. "X" cut on C.M.P. S 60° E 40.98
Fd. "X" cut on C.M.P. S 30° E 22.06
Dbl. hd. nail & disc in Elec. Pole S 70° E 180.87
Dbl. hd. nail & disc in Elec. Pole S 85° W 218.28



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
Signed by Glenn E. Richard Date Oct. 20, 1994
Glenn E. Richard
Surveyor's Michigan License No. 13040