

JAN 25 2000

Filed under Remonumentation Act 345 of 1990 LIBER 1
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 372
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

7 DEC 1999 1:02:41 PM

SECTION

For corners in Lenawee (County)

	Located In:	Corner Code #
1. Public Land Survey	T-6-S R-3-E	D-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on November 16, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This position not established by original government surveyors.
1951 Walter Frazier did a lot survey in the SW 1/4 of Sec. 32 that called for the east line of the lot as being the North & South 1/4 line
1975 I set a R.R. spike in the pavement on a line between East and West 1/4 corners and by retracing the 1951 survey by Walter Frazier and recorded it in Liber 3, Page 377
1991 Werner Sommer set a P.K. nail over the R.R. spike
1998 Lawrence Feindt found the P.K. nail and recorded it in Liber 5, Page 377
July 1999 I witnessed the P.K. nail prior to US-223 reconstruction

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Nov. 12, 1999 I staked location for contractor to set monument box in new asphalt pavement.
Nov. 16, 1999 I set a 5/8" X 3' re-rod with Lenawee County re-mon cap stamped P.S. 13040 in the monument box at the location of the previous recordings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- Fd. P.K. nail & tag stamped 16034 in T.P. S 2° W 59.34
- Fd. P.K. nail & tag stamped 16034 in 6" Cedar S 60° W 129.88
- Fd. 1/2" rod in concrete monument South 98.53
- 1/2" rod South 61.43
- Back of curb 3.3 east of curb inlet North 11.88
- Fd split seam iron set by Walter Frazier in 1951 South 60.81



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date November 23, 1999

Signed by Glenn E. Richard Date Dec. 1, 1999
Glenn E. Richard

Surveyor's Michigan License No. 13040