

DEC 22 1998

SECTION

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 301  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

16 DEC 1998 4:19:13 PM

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T - 6-S R - 3 - E	E-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on November 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824 John Mack set post Cor Secs 20, 21, 28 & 29, W. Oak 30 N 18 E 39, B. Oak 12 S 33 W 4
- 1927 Harold Clegg found large square stone added 1 1/4" iron pipe, 15" Hickory N 27 W 76.35, 12" Hickory S 54 W 48.0, Set iron pipe 33' South
- 1960 I found a spike and iron pipe 33' South
- 1962 Werner Sommer found boat spike
- 1966 I found a boat spike
- 1967+ Jack Gillin (Road Commission employee) found boat spike and set a monument box . 18" Hickory S 45 W 48.83 20" Hickory N 20 W 76.93
- 1972 Werner Sommer found the corner had been destroyed by road construction. He re-established it by re-tracing previous surveys and the iron pipe 33' South. He recorded the corner in L. 1, P. 599, nail in E side 18" Hickory S 55 W 48.74, nail in E. side 18" Hickory N 20 W 76.81
- 1994 Michael Bartolo found the iron pipe and recorded it in L. 5, P. 236

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 4, 1998, Dug through base course of new asphalt. Found 3/4" X 8" iron pipe over boat spike 18" deep. Top of stone 24" deep 0.2 West and 0.2 South, and 1 1/4" iron pipe 26" deep. Replaced boat spike and 1 1/4" iron pipe with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040. Also set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & re-mon tag in 38" Oak S 70° W 86.41
- SE. corner of chimney N 5° W 128.63
- SE. corner of house foundation N 45° W 116.50
- SW. corner of house foundation N 40° E 104.06
- Fd. P.K. in Tel. pole N 65° E 57.97
- Fd. iron pipe South 32.89
- Fd. dbl.hd. nail & disc in Elec. pole South 55.19



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998

Signed by Glenn E. Richard Date Dec. 11, 1998  
Glenn E. Richard

Surveyor's Michigan License No. 13040