

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **33**

For corners in

Lenawee Located In: Corner Code #
 (County)

1. Public Land Survey T 6-S R 3-E F 3
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____
 Property in Sec. S _____ T _____ R _____

FILED
 10:56 AM
 OCT 28 1994
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 8 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set 1/4 Sec. post W. Ash 15 S 3 E 15, B. Walnut 30 N 30 W 24
 J.L. Richard record from 1914 "Found stone, fence post South 39 links, set stone on line between at 1/2 distance between E-3 and F-3.
 April 1976, I dug but couldn't find any trace of the stone. Dug at the 1/8 corner and found the stone surrounded by pieces of tile, Set 3/4" X 4' galv pipe by doubling the distance and extending the line east from the SW corner of Section 4 and the found 1/8 corner and recorded them in L. 3, P. 425.
 "X" cut on C.M.P. S 70° E 80.35 Dbl hd. nail & disc in Elec pole S 25° E 77.18
 Dbl hd. nail & disc in Tel. pole S 15° W 27.65 Dbl hd. nail & disc in Elec. pole N 10° E 87.66

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 10, 1994, Found iron pipe in monument box, top of box missing;
 Top of iron hit and bent. Replaced iron with 3/4" X 3' iron pipe capped G.E. R. P.S. 13040.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe, capped GER P.S. 13040 in monument box, and is accepted as the best available evidence of the position of the original corner.
 Found Dbl. hd. nail & disc in Elec. pole N 10° E 87.56
 Found Dbl. hd. nail & disc in Elec. pole S 25° E 77.12
 Found Dbl. hd. nail & disc in Tel. pole S 15° W 27.58
 "X" cut on C.M.P. S 80° E 80.58
 "X" cut on C.M.P. N 75° E 115.53



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
 Signed by Glenn E. Richard Date Oct. 20, 1994
 Glenn E. Richard

Surveyor's Michigan License No. 13040