

SURVEY & RE-MONUMENTATION

DEC 22 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 302
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6-S R - 3 - E	F-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

16 DEC 1998 4:19:28 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on November 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John Mack set 1/4 post W. Oak 20 S 36 E 26, W. Ash 10 N 49 W 36
 Found no records on this corner before 1948
 1948 Harold Clegg & I did a survey in the NW 1/4 of Section 28 but did not find the corner
 1951 Kenneth Suydam did a survey in the NW corner of the NE 1/4 of Sec 28 and his notes show a point (iron?) on line between the SE and SW corner of Section 21 and 1.4 North of point shown on 1948 survey by Harold Clegg. He set an iron pipe South 46.4'
 1964 & 1965 I found the iron pipe 46.4' South
 1975 Werner Sommer did the Plat of Amsler Woods and retraced Kenneth Suydam's 1951 survey to re-establish the corner.
 1977 I found an iron pipe 10" deep under the pavement and raised it with 1/2" re-rod and recorded it in L. 3, P. 482
 1994 Michael Bartolo found the corner had been destroyed during installation of CMP cross culvert. He used the three remaining witnesses shown on the 1977 recording to set a cotton gin spike and checked distance South to Plat of Amsler Woods.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 4, 1998, I found the cotton gin spike under base course of new asphalt pavement. Replaced it with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' rered with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

"X" cut on N. end C.M.P. N 5° E 21.64
 Fd. nail & shiner in W. face 24" Walnut S 10° E 35.05
 Fd. nail & shiner in E. face Elec. pole S 30° E 64.46
 Fd. nail & shiner in N. face 17" Oak S 75° W 77.30
 Capped (M.J.B. 33970) iron rod South 50.00
 Plat monument South 233.00 feet



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998
 Signed by Glenn E. Richard Date Dec. 11, 1998
 Glenn E. Richard
 Surveyor's Michigan License No. 13040