

JAN 25 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 336  
STATE OF MICHIGAN  
LENAAWEE COUNTY  
FILED

1 SEP 1999 5:44:22 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T -6 - S R - 3 - E	G-2
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on June 7, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mack set 1/4 sec. post Maple 18 S 58° W 24 W. Ash 14 N 19 E 17 ,  
1880 James Blair found large stone  
1920 J.L. Richard surveyed Tipton Hwy. and called for the corner in his description but not type of monumentation  
1959 Kenneth Suydam found large stone. Raised to surface with 8" boat spike and set iron in fence N 89° 18' E 33'  
1979 Kenneth Suydam set RR spike as the boat spike was gone using the angle and distance from the iron pipe 33' east and recorded it in Liber 4, Page 272.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 7, 1999 Found R.R. spike in the pavement . Hit the stone 2 1/2' deep. Bent the bottom of the 5/8" X 3' re-rod to the north side of the stone. Set Lenawee County Re-mon cap on re-rod & set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

Survey mark spike & Lenawee County re-mon tag in post with telephone box S 25° E 76.78  
dbl hd nail & Lenawee County Re-mon tag in 18" Hickory S 25° W 65.26  
dbl hd nail & Lenawee County Re-mon tag in 24" twin Ash N 60° W 31.09  
Cut "X" on N. end CMP N 50° E 26.99



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date July 20, 1999

Signed by Glenn E. Richard Date Aug. 23, 1999  
Glenn E. Richard

Surveyor's Michigan License No. 13040