

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 57

For corners in

Lenawee
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>6-S</u> R <u>3-E</u> | <u>G-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
2:01 P.M.
DEC 05 1994
LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on October 10 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3				●									
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set post cor. Sec. 3, 4, 9 & 10 W. Ash 10 N 62 W 24, W. Oak 24 S 64 E 34.
October 1880, James Blair survey notes "I found a stake & large stone".
J.L. Richard record from early 1900's call for stake & large stone.
June 1959, K.L. Suydam "Found large pointed stone about 1' below surface, raised with drag tooth, spike & washer in 20" Hickory N 59° E 64.95, 30" Elm N 35° W 44.80, 26" Maple S 24° E 52.00, 26" Maple S 49° W 46.00.
March 1976, I probed through the pavement at point located from remaining witnesses and set with 3/4" Iron pipe and recorded it in L.3, P. 423, Dbl. hd. nail & disc in: Tel. pole N 35° W 44.84, 20" Hickory N 65° E 65.70.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 10, 1994, Found 1/2" rod over 3/4" X 12" iron pipe.
November 16, 1994, Found 1/2" re-rod at surface over 3/4" X 12" iron pipe. Replaced re-rod and 3/4" iron pipe and set 3/4" X 3' iron pipe in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3' iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Fd. dbl. hd. nail & disc in Tel. pole N 35° W 44.87
Set dbl. hd. nail & disc in Elec. pole N 25° W 94.93
Set dbl. hd. nail & disc in Elec. pole S 40° E 71.34
Set 60d spike in 40" Maple S 30° W 72.82
Cut "X" on C.M.P. N 40° E 38.42



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994

Signed by Glenn E. Richard Date Nov. 29, 1994
Glenn E. Richard

Surveyor's Michigan License No. 13040