

DEC 22 1998

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 303

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

16 DEC 1998 4:19:49 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Table with columns: Lenawee (County), Located in:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on November 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A black dot is located at the intersection of column G and row 9.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824 John Mack set post Cor. Sec's 21, 22, 27 & 28 B. Oak 20 S 21 E 26, B. Oak 12 N 44 W 49
1920 Walter Frazier found large stone and brick
1927 Harold Clegg found spikes in pavement. Set 1" iron pipe
1951 Kenneth Suydam shows corner on notes (type of monumentation not given)
1957 Kenneth Suydam found a boat spike
1960 I found a spike
1963 I found a spike and raised with iron pipe
1967+ Lenawee County Road Commission placed a monument box
1974 Werner found iron in monument box and recorded it in L. 2, P. 635
1994 Michael Bartolo found 3/4" iron pipe at road surface and recorded it in L. 5, P. 237

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 4, 1998, Found 3/4" X 12" iron pipe over piece of boat spike over 3/4" X 18" galv. pipe. Top of monument box was 6" below base course of asphalt. Raised monument box to the surface with adjusting rings. Replaced found iron pipe with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & re-mon tag in Elec. pole N 25° E 98.68
Fd. nail & shiner in NW. face Util. pole S 60° W 43.07
Fd. nail & shiner in SW. face Util. pole N 40° W 43.23
Fd. RR. spike in N. face Util. pole S 55° E 44.84



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998

Signed by Glenn E. Richard Date Dec. 11, 1998

Surveyor's Michigan License No. 13040