

DEC 22 1998

SECTION

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 307  
 STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

16 DEC 1998 4:20:52 PM

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

For corners in

Lenawee (County)	Located In:	Corner Code #
1. Public Land Survey	T - 6 - S R - 3 - E	G - 12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on November 5, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John Mack Set 1/4 Sec. post B. Oak 6 N 59 W 34, Leverwood 5 S 22 E 24  
 Early 1900's J.L. Richard's record calls for "Stone on end surrounded by others" and 1940's same record as above by Harold Clegg  
 1935 Point of beginning for Assessor's Plat No. 15, City of Adrian  
 1948 Point of beginning for Woodlawn Farm  
 1965 I found a spike, point of beginning for Plat of Rolling Meadows  
 1998 George Avendt P.S. No. 16034 dug found iron pipe and raised to surface with 1/2" X 18" iron rod and Lawrence Feindt recorded it in L5 P370

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

November 5, 1998, Found 1/2" X 18" iron pipe capped 16034 at surface of pavement, in top of 3/4" X 20" iron pipe. Replaced found iron pipe with 5/8" X 3' re-rod with Lenawee County Re-mon cap stamped P.S. 13040 and set monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod in monument box with Lenawee County Re-mon cap stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.

Found plat monument North 33.00  
 Found plat monument South 33.12  
 NW. corner brick apartment building S 25° E 65.29  
 Fd. nail in S. face of Elec. pole N 25° W 23.42  
 Fd. nail in SW. face of 23" Maple N 25° E 42.23



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998

Signed by Glenn E. Richard Date \_\_\_\_\_  
 Glenn E. Richard

Surveyor's Michigan License No. 13040