

**SURVEY &  
REMONUMENTATION**

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **20**

For corners in

Lenawee Located In: Corner Code #  
(County)

- 1. Public Land Survey T 6-S R 3-E Corner Code # H-3  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on October 8 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. January 1824, John Mack set 1/4 post Hickory 7 S 42 W 27, W.Oak 20 N 45 E 8  
July 1948, During a survey for road reconstruction "Found traces of wood stake in line of fences North and South", Fence post South 22.5.  
March 1976, I dug again but the monument had been destroyed during road construction. Set iron pipe 22.5 North as per record from old end post and recorded it in L. 3, P. 423.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

October 8, 1994, Found iron pipe in monument box (top missing) The top of the iron pipe hit and bent. Bottom of iron pipe straight & plumb. Replaced with 3/4" X 3' iron pipe capped G.E.R. P.S. 13040 and placed new top on the box.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

3/4" X 3' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.  
Fd. 60d spike & disc in 8" Walnut N 15° E 59.18  
Set dbl. hd. nail & disc in Elec pole South 50.31  
Cut "X" in C.M.P. N 45° E 24.63  
Cut "X" on top cast iron C.B. Cover S 70° E 132.68  
N. edge of Tel. cable marker post S 30° W 25.29



**FILED**  
OCT 28 1994 10:56 AM  
LENAWEE COUNTY  
JEANETTE D. KNOX  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3								●					
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994

Signed by Glenn E. Richard Date Oct 19, 1994  
Glenn E. Richard

Surveyor's Michigan License No. 13040