

DEC 22 1998

Filed under Remonumentation Act 345 of 1990 LIBER 1  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

PAGE 304  
STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

SECTION

For corners in

16 DEC 1998 4:20:02 PM

| Lenawee<br>(County)                   | Located In:             | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| 1. Public Land Survey                 | T - 6-S R - 3 - E       | H-9           |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous<br>Property in Sec   | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Glenn E. Richard, in a field survey on November 4, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824 John Mack set 1/4 Sec. post B. Oak 10 N 62 W 14, W. Oak 20 S 64 E 19  
1920 Walter Frazier surveyed the road and found lime corner and placed gas pipe 8" Hickory SE 51.6, SE corner of house NW 91.7  
1957 Werner Sommer found spike which checked witnesses and set iron pipe 33' south and another one 321.94 South  
1967+ Lenawee Co. Road Commission set monument box  
1973 Werner Sommer set a P.K. nail in the pavement by retracing his 1957 survey & recorded it in L. 2, P. 359  
1977 Arvin Butterfield set a 3/4" iron pipe in a monument box after sewer construction and recorded it in L. 4, P. 19  
1984 I retraced several surveys and Plats that were tied to this corner before sewer construction and recorded it in L. 5, P. 131


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

June 12, 1998 I found a 3/4" iron pipe in a monument box  
November 4, 1998, Set 5/8" X 3' re-rod inside of the found iron pipe and drove both down. Raised monument box with adjusting rings.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" X 3' re-rod with Lenawee County Remon Cap stamped P.S. No. 13040 in a monument box and is accepted as the best available evidence of the position of the original corner.

SE corner of house foundation N 20° W 97.53  
NW corner of house foundation S 20° E 121.04  
Survey mark spike & remon tag in 16" Maple N 28° W 37.33  
Survey mark spike & remon tag in 20" Hickory S 50° E 51.02  
Iron pipe in Concrete South 33.14  
Fd. nail & disc in 30" Ash N 35° W 36.82



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 1, 1998

Signed by Glenn E. Richard Date DEC 11, 1998  
Glenn E. Richard

Surveyor's Michigan License No. 13040