

SURVEY & REMONUMENTATION

JAN 15 1998

SECTION

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 LENAWEE COUNTY
 FILED

5 NOV 97 11:55 A.M.

VICTORIA J. DANIELS
 REGISTER OF DEEDS

For corners in

| <u>Lenawee</u> (County) | Located In: | Corner Code # |
|------------------------------------|---------------------------------|---------------|
| 1. Public Land Survey | T <u>6</u> - S R - <u>3</u> - E | <u>H-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

LIBER 1 PAGE 218

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Glenn E. Richard, in a field survey on September 18, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | ● | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John M. Mack set 1/4 Sec. post Elm 10 S 49 E 18 W. Oak 5 N 39 W 29
 1884 & 1887 James Blair found stake & bricks
 1904 James Blair survey calls for drag tooth and bricks
 J.L. Richard's record is copy of Blairs
 1936 The corner is shown on Assessor's Plat No. 17, City of Adrian
 1957 W.E. Sommer found iron pipe & raised with Hex iron
 1975 K.L. Suydam found Hex iron and recorded it in L 3 P 305
 1976 I found the hex iron and recorded it in L 3 P 429

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

September 18, 1997 I found a 1/2 X 23" iron pipe in a water box (set by City of Adrian)
 I dug out the water box and found that the 1/2" iron pipe was inside of a 2" x 23" iron pipe 15" deep. Dug to a point 3 1/2' deep but found nothing else set a 3/4" X 3' iron pipe capped G.E.R. 13040 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron pipe capped G.E.R. in monument box and is accepted as the best available evidence of the position of the original corner.

Found dbl. hd. nail & disc in street light pole North 25.77
 Found dbl. hd. nail & disc in E.P. S 20° W 41.89
 "X" cut on face of Fire Hyd. S 30° E 54.75
 NW corner of post at west end of fence S 60° E 88.73
 Plat monument S 45° E 46.86



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 28, 1997

Signed by Glenn E. Richard Date Nov. 3, 1997
 Glenn E. Richard

Surveyor's Michigan License No: 13040