

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

| Lenawee (County) | Located In: | Corner Code # |
|------------------------------------|-------------|---------------|
| 1. Public Land Survey | T-6-S R-3-E | 1-8 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec | S T R | |
| | S T R | |

B JUL 97 1:01 P.M.

VICTORIA J. DANIELS
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Glenn E. Richard, in a field survey on January 24, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 7 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1824, John M. Mack Set 1/4 Sec. post W. Oak 24 N 36 W 34, B. Oak 18 S 10 E 5
 Couldn't find any information on this corner in any of the old survey records.
 1968 (per recording in L.1, P. 101) Consumers Power "dug & found corner, set pinch top iron".
 October 1970, Ken Suydam found pointed stone and iron pipe 0.25 North of the stone.
 January 1972, Werner Sommer found pinched top iron & recorded it in L. 1, P. 101.
 August 31, 1994, The road had been graded. I found a 1/2" X 6" iron pipe. I set a monument box as the road commission was paving.
 September 13, 1994, I found a stone under the monument box at the location of the short 1/2" X 6" iron pipe, I split the stone and set a 5/8" X 2' re-rod.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Jan 24, 1997 found 5/8" re-rod capped G.E.R. 13040 in monument box and verified location by checking distances North and South to section corners and West to nail in E.P.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5/8" re-rod capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Dbl. hd. nail & disc in E. P. N 20 W 130.19
 Fd. dbl. hd. nail & disc in E. P. West 34.15
 " X " cut on south end of C. M. P. S 45 E 33.19
 Fd. re-rod East 33.14

SURVEY &
REMONUMENTATIO

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97
Glenn E. Richard

Surveyor's Michigan License No. 13040