

**SURVEY & REMONUMENTATION**

JAN 15 1998

Filed under Remonumentation Act 345 of 1990  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 LENAWEE COUNTY  
 FILED

SECTION

22 DEC 97 9:24 A.M.

For corners in

<u>Lenawee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6-S</u> R <u>3-E</u>	<u>1-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

VICTORIA J. DANIELS  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on Dec. 5, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, John Mack set post cor. Sec. 26, 27, 34 & 35, B.Walnut 20 S 83 E 26 Basswood 22 N 55 W 20
- 1889 James Blair found a stone pump
- J.L. Richard's record same as J. Blair's
- 1936 Point of beginning for Assessor's Plat No. 17, City of Adrian
- 1950 Point of beginning for Adrian Heights
- 1954 W.E. Sommer under direction of W.E. Frazier found corner (type of monumentation not given) and set iron pipe's 47.1' east and another 141.65 farther east
- 1955 Point of beginning for Broadview Terrace

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Dec. 3, 1997 Found 3/4" iron pipe which checked witnesses I had taken in 1989. Found the iron pipes set by W.E. Sommer in 1954 which checked to found iron pipe at the section corner.
- Dec. 5, 1997 Dug and found 1 1/4" iron pipe in concrete 2' deep with the found 3/4" iron pipe driven in the top of the 1 1/4" iron pipe. Couldn't get the 3/4" iron pipe out so left it and poured 4" deep concrete at the surface around the found 3/4" iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" iron pipe capped G.E.R. 13040 in concrete over 1 1/4" iron pipe in concrete and is accepted as the best available evidence of the position of the original corner.

- Survey mark spike & re-mon tag in E.P. S 65° W 76.38
- Fd. dbl hd nail & disc in E.P. N 30° W 24.02
- SW corner foundation, Hse #690 N 25° E 85.81
- NW corner foundation, Hse #610 N 70° E 129.45
- Iron pipe East 47.09
- Iron pipe East 188.78
- Iron pipe on North side of 4" Pine North 33.17
- Back of curb south 5.85



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date December 16, 1997

Signed by Glenn E. Richard Date 12-17-97  
 Glenn E. Richard

Surveyor's Michigan License No. 13040