

SURVEY & REMONUMENTATION

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **36**

For corners in

<u>Lenawee</u>	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>6-S</u> R <u>3-E</u>	<u>L-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED 10:56 AM

OCT 28 1994

LENAWEE COUNTY
JEANETTE D. YNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 10 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. January 1824, John Mack set 1/4 post Elm 6 S 38 W 3, Hornbean 4 N 75 E 10.
October 14, 1879, G.E. Kedzie, County Surveyor, called for stone.
1907, J.L. Richard records "found old corner under tree" and another record not dated as stone.
July 1948, The notes from a survey for road construction call for "Found near surface" (no description), Concrete fence post South 30.2, 14" Hickory S about 30° E 36', 16" Elm S about 30° W 33.5
March 1950, W.E. Frazier notes: "This road was graded +". He re-established the corner from the witnesses and the stakes that were set on the road survey and staked a lot on the north side of the road.
November 1971, W. E. Sommer found a p.k. nail in the pavement and the iron pipe set by W.E. Frazier 33' North and recorded in in L. 1, P. 73.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

October 10, 1994, Found iron pipe in monument box, which checks the witnesses on the L.C. R.C. recorded by W.E. Sommer.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 4' iron pipe capped G.E.R., P.S. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
Fd. 60d spike in 18" Hickory S 55° W 41.71
Fd. 60d spike in 18" Hickory N 25° W 42.83
Set dbl. hd. nail & disc in Elec. pole North 30.58
Cut "X" on C.M.P. S 40° E 24.65
Fd. iron pipe North 33.00



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date October 13, 1994
Signed by Glenn E. Richard Date Oct. 20, 1994
Glenn E. Richard

Surveyor's Michigan License No. 13040

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1993