

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

8 JUL 97 1:00 P.M.

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Lenawee  
(County)

Located In:

Corner Code #

1. Public Land Survey	T - 6 - S	R - 3 - E	L-11
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec	S	T	R
	S	T	R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on May 1, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G.L.O. 1824, John Mack set 1/4 Sec. post W. Oak 10 N 36 E 44, Elm 18 S 7 E 36
- 1916 J.L. Richard set ford axle
- 1927 Fred Soll found ford axle during survey for Girls Training School and replaced it with a conc. monument with brass cap.
- 1942 W.E. Frazier used the corner but didn't describe the type of monumentation.
- 1962 K.L. Suydam and I found the monument on east side of old North-South fence.
- 1971 W.E. Sommer found the monument.
- 1972 W.E. Sommer found the monument while doing a survey for the City of Adrian.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- February 12, 1997, Found iron pipe set by W.E. Frazier & Assoc. by using a combination of the information from the 1942 W.E. Frazier survey and the 1971 W.E. Sommer survey. I tied the iron pipe to the irons that could be found on the survey by W.E. Sommer in 1972.
- February 13, 1997, dug with backhoe (furnished by the City of Adrian) but didn't find anything except a piece of strap iron 3 1/2' deep lying flat.
- February 14, 1997 I tied W.E. Sommer surveys of 1971 & 1972 to a boat spike I set on the 1962 survey. I computed the location of the corner from the W.E. Sommer 1972 survey which agrees with the location of my 1962 survey and set a re-rod.
- May 1, 1997, Replaced the re-rod with a 30" Harrison monument stamped P. S. 13040

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 30" Harrison monument stamped P.S. 13040 and is accepted as the best available evidence of the position of the original corner.
- "X" cut on face of chain link fence post N 30° E 16.92
- "X" cut on face of chain link fence post S 55° E 9.78
- P. K. nail in top of C. M. P. N 35° W 9.33
- Re-rod on corner of Oakwood Rd. South 467.77
- Carsonite marker post in N-S fence East 8.0'
- East edge of pavement West 7' +/-

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

SURVEY & REMONUMENTATION

AUG 25 1997

COMMISSION



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 6-3-97

Signed by Glenn E. Richard Date 6-9-97  
Glenn E. Richard

Surveyor's Michigan License No. 13040