

JAN 25 2000

Filed under Remonumentation Act 345 of 1990  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

LIBER 1 PAGE 311

STATE OF MICHIGAN  
LENAWEE COUNTY  
FILED

14 JUL 1999 6:30:15 PM

VICTORIA J. DANIELS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in	Located In:	Corner Code #
<u>Lenawee</u> (County)		
1. Public Land Survey	T <u>6 - S</u> R <u>3 - E</u>	<u>M - 11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Glenn E. Richard, in a field survey on April 19, 1999, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A B C D E F G H I J K L M

1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. 1816 Joseph Fletcher set post cor. Sec's 25 & 26 W. Oak 6 N 32 W 40 B. Oak 6 S 84 E 35  
 1875 Burton Kent (Co. Surveyor) did a survey of the NE 1/4 of Section 36 & notes state (the corner being obliterated) the Section cor. was established "in the center of said line between the 1/4 posts"  
 1924 Walter E. Frazier did survey in SE 1/4 of Sec. 25 and described the corner as gas pipe & stones  
 1927 Fred Soll surveyed sections 25 & 26 for the Girls Training School. Survey shows found iron pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 19, 1999 I retraced part of Fred Soll's survey and found a 4" brass cap in the top of a 4" iron pipe stamped "State of Michigan, Southeast corner Sec. 25 surrounded by stones. I left the monumentation as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" brass cap in top of 4" iron pipe and is accepted as the best available evidence of the position of the original corner.

- dbl hd nail & re-mon witness tag in 14" Walnut S 20 W 43.22
- dbl hd nail & re-mon witness tag in 10" W. Cherry S 40 W 28.04
- dbl hd nail & re-mon witness tag in 18" Oak S 80 W 90.73
- Survey mark spike & re-mon witness tag in 20" Oak North 29.26
- 333'± South to centerline of Oakwood Rd.
- A-12 6-4 South 348.48



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999  
 Glenn E. Richard

Surveyor's Michigan License No. 13040