

MAY 1 6 1997

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE LIBER 1 PAGE 159

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Lenawee
(County)

Located in:

Corner Code #

STATE OF MICHIGAN
LENAWEE COUNTY
FILED

17 DEC 96 9:20 A.M.

JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 1. Public Land Survey T-6-S R-3-E
T-7S R-3 E
T-____ R-____
T-____ R-____
- 2. Property Controlling S-____ T-____ R-____
in Section S-____ T-____ R-____
- 3. Miscellaneous S-____ T-____ R-____
Property in Sec S-____ T-____ R-____

M-13
M-1

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on October 31 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 G.L.O. Feb. 1816, Joseph Fletcher set post corner T6S-R3 & 4E, Hick. 12 N 16 W 35, Elm 8 S 59 E 55
 James Blair records show B. Kent established the corner in 1876 on straight line between the E 1/4 corner Sec. 36, T6S-R3E and the SE. cor. of Sec. 1, T7S-R3E (Type of monumentation is not noted).
 1907 J.L. Richard records "Drove gas pipe".
 1941, Harold Clegg (W.E.F. employee) "Found old wood stake, drove boat spike".
 April 5, 1995, I dug and found a boat spike 8" deep which checked the two remaining witnesses of H. Clegg and drove 3/4" X 24" iron pipe over the spike.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 October 31, 1996, I found the 3/4" X 24" iron pipe under a new asphalt pavement. Replaced it with a 3/4" X 3' gas pipe capped G.E.R. 13040 and set a monument box.
 This is a common corner with M-1, T7S-R3E.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" X 3' gas pipe capped G.E.R. 13040 in monument box and is accepted as the best available evidence of the position of the original corner.
 Dbl. hd. nail & disc in S. side 36" Maple S 85° W 21.75
 Dbl. hd. nail & disc in E. side 46" Maple S 40° W 68.06
 Nail & token in S. side Elec. pole N 75° E 25.05
 Dbl. hd. nail & re-mon tag in W. side Elec. pole S 10° E 170.11
 3/4" X 3' gas pipe in monument box at M-2, T7S-R3E, South 263.10



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 10-08-1996
 Signed by Glenn E. Richard Date 12-11-96
 Glenn E. Richard
 Surveyor's Michigan License No. 13040