

RECORDED

JAN 25 2000

SECTION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 312
STATE OF MICHIGAN
LENAWEE COUNTY
FILED

For corners in

Lenawee
(County)

Located In:

Corner Code #

14 JUL 1999 6:30:31 PM

VICTORIA J. DANIELS
REGISTER OF DEEDS

- 1. Public Land Survey T 6 - S R 4 - E A-12
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Glenn E. Richard, in a field survey on June 21, 19 99, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. This position not established by original government surveyors
 1875 Burton Kent (Co. Surveyor) did a survey of the NE 1/4 of Section 36 T6S R3E & shows jog of 5.28 chains (348.48')
 1882 James Blair set a stake and bricks W. Oak 4 S 11 1/2 W 45 1/4 lks (29.86')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

April 27, 1999 I re-established the corner on line between the W 1/4 corner and NE corner of Section 36 T6S R3E and at the record jog shown on Burton Kent's 1875 survey. The corner falls 5.5'± South of the pavement.
 June 21, 1999 Set 30" Harrison monument

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

30" Harrison monument stamped P.S. 13040. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
 spike & re-mon tag in 26" Oak S 10 W 26.47
 spike & re-mon tag in T.P. West 84.52
 P.K. re-mon tag in Top of guard rail post N 10 E 29.29
 Survey mark spike & re-mon tag in T.P. S 55 E 21.88
 Carsonite post South 5.0
 M-11 North 348.48



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date June 22, 1999

Signed by Glenn E. Richard Date July 8, 1999
 Glenn E. Richard

Surveyor's Michigan License No. 13040