

NOV 07 1994

COMMISSION

Filed under Remonumentation Act 345 of 1990

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 001 PAGE 26

For corners in

Lenawee (County)

Located In:

Corner Code #

- 1. Public Land Survey T-6-S R-4-E B-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, Glenn E. Richard, in a field survey on September 26 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Corner was not set on G.L.O. survey

Section 6, T6S-R4E was subdivided in February 1834 as shown on survey in Satterthwaite record book but the monuments are not described.

March 27, 1974, Werner Sommer set iron pipe in the pavement on extension of fence line from the south and on the line between the Southwest corner and the South 1/4 corner of Section 31, T5S-R4E, he recorded it in L. 2 on P. 611.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

11-9-93 & 12-13-93, Found 3/4" re-rod in monument box. The road was excavated to a depth of 2'± during construction 2 years ago, and all witnesses destroyed.

Retraced surveys done previously and found re-rod in the box to be 0.22 South of original location. Removed re-rod and set 3/4" X 3" iron pipe capped P.S. 13040, at original location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" X 3" iron pipe capped P.S. 13040 in monument box. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- SW corner of stone foundation of house N 50° E 136.19
Fd. spike in East side 18" Hickory South 41.33
Dbi. hd. nail & disc in South side Elec pole N 80° W 255.90
Dbi. hd. nail & disc in West side Elec pole N 50° E 48.00
S 1/4 corner Sec. 31, T5S-R4E East 321.01



Ratified by Peer Group in accordance with P.A. 345

Co. Rep. Glenn E. Richard

Date 9-29-1994

Signed by Glenn E. Richard

Date Oct 10, 1994

Surveyor's Michigan License No. 13040

FILED

10:52 AM

OCT 28 1994

LENAWEE COUNTY
JEANETTE D. KNOX
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. Cell (2, A) contains a black dot.