

SURVEY & REMONUMENTATION COMMISSION
 NOV 07 1994

Filed under Remonumentation Act 345 of 1990
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER **001** PAGE **27**

For corners in Lenawee Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 6-S R 4-E C-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

FILED 10:56 AM
 OCT 28 1994
 LENAWEE COUNTY
 JEANETTE D. KNOX
 REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1 | | | ● | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Glenn E. Richard, in a field survey on September 26 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO June 1819, Joseph Fletcher set post W. Oak 14 S 33 E 51, W. Oak 20 S 58 W 39 Section 6, T6S-R4E was subdivided in February 1834 as shown on survey in Satterthwaite record book but the monuments are not described.
 March 1887, Survey by James Blair states he sighted to the corner but didn't describe the monument.
 J.L. Richard records from early 1900's called for stake.
 W.E. Frazier set iron pipe in late 1940's or early 1950's from record witnesses.
 March 27, 1974 Werner Sommer found spike over iron pipe and recorded the corner in L 2, P 611.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 11-9-93 & 12-13-93, Found 3/4" re-rod in monument box. The road was excavated to a depth of 2'± during construction 2 years ago, and all witnesses destroyed.
 Retraced surveys done previously and found re-rod in the box to be 0.06 North and 0.17 West of original location.
 Removed re-rod and set 3/4" X 3" iron pipe capped P.S. 13040, at original location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 3/4" X 3" iron pipe capped P.S. 13040 in monument box and is accepted as the best available evidence of the position of the corner.
 Found spike in Elec pole N 65° E 131.6
 Dbl. hd. nail & disc in Elec pole S 50° E 127.2
 NE corner of conc step S 40° E 94.26
 Found 3/8" iron pipe on Section line South 33.01
 SE corner Section 31, T5S-R4E East 379.21
 NW corner house found. S 20° E 91.27



Ratified by Peer Group in accordance with P.A. 345 Co. Rep. Glenn E. Richard Date 9-29-94
 Signed by Glenn E. Richard Date Oct. 10, 1994
 Surveyor's Michigan License No. 13040